



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu
राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba – 181143, Jammu (J&K)

No: CUJ/W/2021/2285

Date: 17.11.2021

.....
.....
.....

Sub:- Quotation

Name of Work : Repair of Cabin of Assistant Professor Sh. Ajay Singh ,CCRC in Central University of Jammu,Bagla Rahya suchani , Distt. Samba.

Dear Sir

The CUJ intends to take up the **Repair of Cabin of Assistant Professor Sh. Ajay Singh ,CCRC in Central University of Jammu,Bagla Rahya suchani , Distt. Samba** and therefore, you are requested to quote the price in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered.

Bidder are required to submit following document along with Quotation:


1. Covering letter in Company letter head format
2. GST Registration/ Pan Card/Aadhar Card
3. Contact Information of bidder(Complete address and Phone no.)


The completion period is 15 days.

Last date of submission of Quotation is 26/11/2021.

Validity of Quotation is 45 days

Encl: As Above


(Er. Vishal Bagotra)
Executive Engineer



**Name of Work : Repair of Cabin of Assistant Professor Sh. Ajay Singh ,CCRC in Central University of
Jammu, Bagla Rahya suchani , Distt. Samba**

S.no	description	unit	quantity	rate	Amount
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.	sqm	20	20.85	417
2	12 mm cement plaster of mix 1:4	sqm	25	294.85	7371.25
3	Providing and applying plaster of paris putty of 2 mm thickness over plastered surface to prepare the surface even and smooth complete.	sqm	20	214.3	4286
4	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade : Two or more coats on new work	sqm	50	137.85	6892.5
	1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	Cum	2.5	6050.65	15126.63
	Providing and fixing pre-coated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams persqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-incharge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.	Sqm	5	671.55	3357.75
	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	25	93.05	2326.25
	Total amount				39777/-

Pawan Kumar

Estimated Cost	39777/-
overall percentage : "At Par" or "Above" or "Below" in figures, quoted by Contractor	

Reman...