



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

No: CUJ/W/2022/3004

Date: 08.04.2022

Sub: - Quotation.

Name of Work: Dry Wall Partition work in Department of PPPA Central University of Jammu, Rahya Suchani,
Bagla.

Dear Sir,

CUJ invites quotation for Providing & Fixing of Dry wall partition/Gypsum Partitions in PPPA department of Central University of Jammu, Rahya Suchani, Bagla. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

- 1.The completion period is 14 days (Fourteen days) from the date of issue of work order.
- 2.The Estimated cost of work is Rs45289.00
- 3.Last date of submission of Quotation is 19/04/2022 at 12:00 hrs
- 4.Date of Opening of Quotation is 19/04/2022 at 15:00 hrs or as decided by Convenor LPC.
- 5.Validity of Quotation is 45 days from the date of opening of Quotation.
- 6.Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site..
- 7.Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
- 8.Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
- 9.No advance payment will be made.
10. GST Bill should be provided.
11. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.
12. Payment shall be made through RTGS/NEFT




जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

13. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip
14. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.
15. Bidders are required to submit following document along with Quotation:
- Covering letter in Company letter head format.
 - GST Registration/ Pan Card/Aadhar Card
 - Contact Information of bidder (Complete address and Phone no.)

Encl: As Above


08/04/2022
(Er. Vishal Bagotra)
Executive Engineer

CC: Guard File
Notice Board



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

BOQ for Dry Wall Partition work in Department of PPPA Central University of Jammu, Rahya
Suchani, Bagla (Annexure-1)

S No	Description	Unit	Qty	Rate (Rs)	Amount (Rs)
1	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-charge.	SQM	24.34	46.5	1131.81
2	Providing and fixing partition upto ceiling height consisting of G.I. frame and required board, including providing and fixing of frame work made of special section power pressed/ roll form G.I. sheet with zinc coating of 120 gms/sqm(both side inclusive), consisting of floor and ceiling channel 50mm wide having equal flanges of 32 mm and 0.50 mm thick, fixed to the floor and ceiling at the spacing of 610 mm centre to centre with dash fastener of 12.5 mm dia meter 50 mm length or suitable anchor fastener or metal screws with nylon plugs and the studs 48 mm wide having one flange of 34 mm and other flange 36 mm and 0.50 mm thick fixed vertically within flanges of floor and ceiling channel and placed at a spacing of 610 mm centre to centre by 6 mm dia bolts and nuts, including fixing of studs along both ends of partition fixed flush to wall with suitable anchor fastener or metal screws with nylon plugs at spacing of 450 mm centre to centre, and fixing of boards to both side of framework by 25 mm long dry wall screws on studs, floor and ceiling channels at the spacing of 300 mm centre to centre. The boards are to be fixed to the frame work with joints staggered to avoid through cracks, M.S. fixing channel of 99 mm width (0.9 mm thick having two flanges of 9.5 mm each) to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and two coats of primer suitable for board as per manufacture's specification and direction of engineer in charge all complete. 2 9.105.2 : 75mm overall thickness partition with 12.5 mm thick double skin tapered edged plain Gypsum plaster board conforming to IS: 2095: (part I): 2011 (Board with BIS certification marks)(makes USG boral, Saint Gobain, Vans Gypsum)	SQM	22.9	1530.05	35038.145

Handwritten signature



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

3	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) : 21.1.1 For fixed portion 21.1.1.1 Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15	KG	5	433.95	2169.75
4	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) 21.1.2.1 Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	KG	9	531.8	4786.2
5	Providing and fixing 12 mm thick pre-laminated particle board flat pressed three layer or graded wood particle board conforming to IS:12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of engineer in-charge. 21.2.2 Pre-laminated particle board with decorative lamination on both sides.(Makes Merino, Century Ply, Ecoboard,Greenlam, Archid, Action Tesa)	SQM	0.4	951.05	380.42
6	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. (Cost of aluminium snap beading shall be paid in basic item):21.3.2 With float glass panes of 5 mm thickness (weight not less than 12.50 kg/sqm) (Modiguard, Saint Gobain, Asahi,Pilkington)	SQM	0.9	1325.55	1192.995
7	Aluminium handle	nos	2	60	120
8	aluminium lock	nos	1	350	350
9	t- bolt	nos	2	60	120
	total				45289.32

DK



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: Dry Wall Partition work in Department of PPPA Central University of Jammu, Rahya Suchani, Bagla

Estimated Cost: Rs45289/- (Rupees Forty five thousand two hundred and eighty nine only)

Estimated Cost (Inclusive of GST)	Quote Percentage (Above/At Par/Below)	
	In figures	In words
Dry Wall Partition work in Department of PPPA Central University of Jammu, Rahya Suchani, Bagla as per BOQ		

Signature & Stamp of the vendor